

Published in SPL Tender No. SPL-2018-02-0086 Dated 14/02/2018

Saraswaty Press Limited invites Sealed Tender from experienced Civil Contractor for Renovation 172X70=12040 Sqft. Thickness 5" RCC Floor with Binding of Steel Work at Unit- III ( Madhyamgram Unit) . The scope of work is attached herewith. The contractors must have ESI, PF and all other statutory compliance. Offer should be sent within 21/02/2018 by 2 p.m. to the Purchase Committee, Saraswaty Press Limited, 11, B.T.Road, Kolkata- 700056 , Phone 2564-7469 & open on the same day. The company reserve the right to accept, negotiate or reject any or all offer with any vendor at its own discretion.

**SARASWATY PRESS LTD**  
**11, B.T. ROAD, KOLKATA-700 056**

**NAME OF WORK : 172x70=12040 sqft THICKNESS 5" RCC FLOOR WITH BUINDING OF STEEL WORK AT SPL - III MADHYAMGRAM UNIT.**

Sl. No.	DESCRIPTION OF WORK	QUANTITY	UNIT	RATE	AMOU
1	Supplying ready mixed concrete of M 25 Grade with well graded stone chips of 20 mm nominal size containing designed quantity of cement per Cu.m of wet concrete produced in computerised batching plant under controlled condition using approved super plastisizer, designing concrete mix following I.S. 10262 and I.S. 456, transporting the mix with agitation in transit mixer to work site depositing the mix on a platform erected for the purpose at required levels of concreting and then placing the mix in its final location of form work compacting and curing the same complete as per specification & direction of the Engineer-in-charge including computerised batching plant transit mixer with all accessories vibrators etc. inclusive of all other incidental charges in this connection complete but excluding cost of hire charge of platform and its supporting staging which would be paid through separate item [cement to be supplied by the Manufacturer/ supplier]	149.75	cum		
2	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (i) Tor steel/Mild Steel	6463	Kg		
3	(A) Filling in foundation or plinth by silver sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity)	110.6	cum		
<b>Total</b>					
Add GST					
Gross Total					